



# *Accelerator Complex of Joint Project in Japan*

*Yoshiharu Mori ( KEK )*


## Configuration of the Accelerator Complex




# Plan View of the Facility



# Site View of the Project



# World's Proton Accelerator



# Requirement



- ~ 50-GeV, 15  $\mu$ A, slow and fast extraction  
for nuclear and particle physics experiments
- ~ 1 MW(~ GeV), <1  $\mu$ s, ~ 25 Hz  
for spallation neutron source

# *Features of the Accelerator Complex*



- *Synchrotron based cascade system*  
--> *suitable for the several-ten GeV machine*

**LINAC + RCS**<sub>(Rapid Cycling Synchrotron)</sub> + **MR** (Main Ring)  
**400(600)MeV**      **3GeV**      **50GeV**

# RCS vs AR advantages



- Lower Beam Current ( Higher Beam Energy)
- Lower Injection Energy
- Higher Injection Beam Loss is allowed.  
(If one increases the beam energy by a factor of 7.5 times, the allowed beam loss during the injection is 7.5 times as high as that for AR with the same beam power.)
- Perhaps immune against the e-p instability

# RCS vs AR      disadvantages



## RCS Challenges


- Lower injection energy in turn implies higher space charge effect. Large aperture magnets are required, giving rise to large fringing fields.
- Powerful RF accelerating system
- Ceramics vacuum chamber with RF shield to avoid the eddy current effect
- Stranded coil to overcome the eddy current effect on the magnet coils.
- Precise magnet field tacking is necessary for each family of magnets

# Proton Linac Requirements



- Current
  - Average **675 μA**
  - Peak **50 mA**
- Pulse
  - Pulse width **500 μsec**
  - Repetition **50 Hz**
  - Chopping ratio **54 %**
  - RF duty (600 μsec ) **3%**
- Beam
  - Energy **400 MeV**
  - Momentum width  **$\Delta p/p = \pm 0.1\% (100\%)$**
  - Emittance  **$3 \pi \text{ mm-mrad} (99\%)$**

# Proton linac



# Features of the Linac Design



## Conflicting Requirements

- Higher accelerating frequency is preferable
  - lower bunch current
  - short focusing period
- Electromagnet is preferable in order to keep the flexible knob  
(Large Drift Tubes, Lower frequency)
  - Both the equipartitioning and constant phase advance are realized
  - The parametric resonance can be avoided

# Coil of Electromagnet in Drift Tube



The coil is electroformed and  
Wire-cutted.

# Issues of the Linac Design



- Beam loss, and beam quality degradation arise at the transitions
- Beam halos arise from the mismatching
  - >Longitudinal transition (200 MeV from SDTL to ACS) is separated from the transverse transition (50 MeV from DTL to SDTL)
  - >1% amplitude control, 1-degree phase control, ~ ~~50~~ mm alignment (perhaps actually ~ 0.1 mm at best), axial symmetry

# Technics Supporting Design Features




- **$\pi$ -mode stabilizing loop (PISL)**
- **High-quality electroplating technique (PR-method)**
- **Electroformed coil**
- **Axially symmetric high-energy accelerating structure:  
Annular-Ring Coupled Structure (ACS)**
- **Chopping system**


# Focusing scheme in the DTL



Phase advance (degree)




Phase advances in the DTL for equipartitioning and constant phase-advance focusing schemes.



Required magnetic field gradient for equipartitioning and constant phase-advance focusing schemes.

# Cs-seeded Ion Source




# 30mA RFQ



The 30mA RFQ  
installed in the test area

Inside view of the RFQ  
stabilized with PISLs




# Emittances at the RFQ exit






At I = 11 mA

horizontal




vertical




normalized  $4_{\text{rms}}=0.69$  -mm-mrad

$4_{\text{rms}}=0.78$  -mm-mrad

# MEBT Photograph



# DTL Tank 1 with DT's Installed



## Comparison of the Lattice Parameters of the 3-GeV Synchrotron (1)



----- The Circumference is increased by a factor of 10/9 -----

	New Lattice	Previous
Circumference	<b>348.3 m</b>	313.5 m
Typical Tune	(6.72, 6.35)	(7.35, 5.8)
Transition Gamma	<b>9.17</b>	<b>9.05</b>
Maximum RF Voltage	<b>450 kV</b>	<b>420 kV</b>
Maximum RF Voltage per Cavity	<b>42 kV</b>	<b>42 kV</b>
The Number of RF Cavities	<b>11 (+1)</b>	<b>10 (+1)</b>

## Comparison of the Lattice Parameters of the 3-GeV Synchrotron (2)



----- The Emittance is increased by a factor of 3/2 -----

	New Lattice	Previous
<b>Painting Emittance at Injection(<math>\pi</math> mm.mrad)</b>	<b>216</b>	<b>144</b>
<b>Collimator Acceptance</b>	<b>324</b>	<b>216</b>
<b>Physical Aperture</b>	<b>486</b>	<b>324</b>
<b>Bunching Factor with 2nd harmonic</b>	<b>0.41</b>	<b>0.41</b>
<b>Incoherent Tune Shift with</b>	<b>0.16</b>	<b>0.23</b>
<b>Bunching Factor without</b>	<b>0.27</b>	<b>0.27</b>
<b>Incoherent Tune Shift</b>	<b>0.24</b>	<b>0.35</b>


## Comparison of the Lattice Parameters of the 3-GeV Synchrotron (3)




The Emittance is increased by a factor of 3/2, while the gap of the BM is as it is.  
The number of families is increased.

	New Lattice	Previous
<b>Bending</b>		
The Number of Magnets	<b>24</b>	<b>24</b>
Gap Height	<b>210 mm</b>	<b>210 mm</b>
Good Field Region	<b>200 mm</b>	<b>190 mm</b>
<b>Quadrupole</b>		
The Number of Magnets	<b>63</b>	<b>66</b>
The Number of Families	<b>11</b>	<b>7</b>


# RCS Configuration




# Beta Function of RCS



# Dispersion Function of RCS



# R&D Dipole Magnet for 3-GeV Synchrotron



Repetition rate : 25[Hz],

Core length : 1.0[m],


Gap height : 210[mm]

Max. field : 1.1[T] ( at 3GeV ) , Min. field : 0.27[T] ( at 400MeV )


# Specifications of 50 GeV Main Ring

*injection energy*  
*extraction energy*  
*# of protons*  
*repetition rate*  
*ave. beam current*  
*beam power @50GeV*  
*superperiod*  
*harmonic number*  
*rf frequency*

3 GeV  
50 GeV (40 GeV @phase I)  
 $3.3 \times 10^{14}$  ppp  
0.3 Hz (~3.6 sec)  
15  $\mu$ A (@slow beam extr.)  
0.75 MW  
3  
9  
1.68MHz(inj.)-1.73MHz(ext.)



# *Acceleration Cycle*




P1 - P2(injection)	0.14 s
P2 - P3(acceleration)	1.9 s
P3 - P4(extraction)	0.7 s
P4 - P5	0.9 s
total	3.64 s

*slow beam extraction*

duty factor	0.20
average current	15 $\times$ A

## Injection/Extraction Scheme for 50 GeV Ring



# Minimization of Beam Loss : key issue for reality

“radiation safety” & “maintenance”

beam loss-> \* controlled : localized and shielded (cf. ESS at extraction)

\* uncontrolled : whole ring ~1W/m

allowed beam losses :

-Injection	135W	0.3%	cont.
-collimator	450W	1%	cont.
-ring	0.5W/m	0.36%	uncont.
-slow beam ext.	7.5kW	1%	cont.
-fast beam ext.	1.125kW	0.15%	cont.
total	8.9kW	2.7%	@slow beam ext.
	2.5kW	1.8%	@fast beam ext.

# Residual Radiation Activity

*example -> 3-50GeV BT collimator*



- . Inner side @ Jaw

> 0.1Sv/h (beam loss 0.45kW)

- . Outer shield surface

shield : 45cm iron


~3mSv/h




\* after 1day cooling off following 30days operation

# Radiation Shield at Beam Extraction Area

*slow extraction*



*fast extraction*



# *What causes beam loss?*



## *Beam Dynamics:*

*high intensity beam behaviors*

- *Space Charge Effect*

- coherent, incoherent, non-linearity, halo formation*

- *Instabilities*

- microwave, e-p, coupled bunch, etc.*

- *others?*

*large acceptance*

- *fringe-field effect*

# *Space Charge Effect -Laslett tune shift(spread): $\Delta Q$ -*

. 50GeV MR

$$\Delta Q = -0.14$$

\*emittance  $54 \pi \text{mm.mrad}$

\*beam intensity  $3.3 \times 10^{14} \text{ ppp}$

\*bunching factor 0.27

\*form factor 1.7

$$\Delta Q = -\frac{r F N_p}{\pi \epsilon \beta^2 \gamma^3 B_f}$$

. 3GeV RCS (for 50GeV MR)

$$\Delta Q = -0.22$$

\*emittance  $144 \pi \text{mm.mrad}$

\*beam intensity  $8.3 \times 10^{13} \text{ ppp}$

\*bunching factor 0.42

# Emittance & Acceptance for 50GeV PS

	<i>emit.</i> $(\pi \text{mm.mrad})$	<i>nor. emit.</i> $(\pi \text{mm.mrad})$	<i>collimator accep.</i>	<i>physical accep.</i>
<i>3GeV PS</i>				
<i>injection</i>	144	146	324	486
<i>extraction</i>	54(core)	220	1.5times	486
<i>3GeV BT</i>				
<i>collimator</i>	54	220	54	120
<i>50GeV PS</i>				
<i>injection</i>	54	220	54-81	81
<i>extraction</i>	10	330	1.5times	81
<i>(30GeV)</i>				
<i>extraction</i>	6.1	330	-	81
<i>(50GeV)</i>				

# Lattice of 50GeV PS

\*Imaginary transition gamma :


$\gamma \rightarrow 32i$  (no transition energy )

\* Negative dispersion at bending magnets :

missing-bend structure

\*Zero dispersion at straight section:



non synchro-beta coupling




# Layout of Magnets -Missing Bend. Mag. Section-

50 GeV Ring


--- 1 Module (15°) of the Arc ---




# *Layout of Magnets -straight section (RF & fast. ext.)-*



## *Tunnel -cross section-*



*arc section*



*staright section*

# *Hardwares*

## *1) Magnets*

*1.9 T - D magnet, large bore Q magnet*

## *2) Magnet Power Supply*

*low ripple & 100% power factor with IGBT*

## *3) RF System*




*High gradient RF cavity with Magnetic Alloy*

## *4) Electro-static Septum*

*Small beam loss at slow beam extraction*

# Dipole Magnet for 50GeV MR (R&D)


<i>gap Height</i>	<i>106mm</i>
<i>useful Aperture</i>	<i>120mm</i>
<i>field length</i>	<i>0.143-1.9T</i>
<i>length</i>	<i>5.85m</i>
<i>weight</i>	<i>34 ton</i>





*good agreement with calculations!*

# Quadrupole Magnet of 50GeV PS (R&D)

Bore Radius    63mm  
Useful Ap.    132mm  
Max. Field    18T/m  
Length(max.) 1.86m



# Vacuum Chamber



*bending magnet*

*quadrupole magnet*

# Magnet Power Supply



---

\* development of new type high power switching devices  
*(IGBT, IEGT)*

<i>accelerator</i>	<i>year</i>	<i>spec.</i>	<i>w.f.</i>	<i>conv.</i>
<i>INS-ES</i>	<i>1962</i>	<i>21.5Hz</i>	<i>sin.</i>	<i>MG</i>
<i>KEK-booster</i>	<i>1974</i>	<i>20Hz</i>	<i>sin.</i>	<i>SCR</i>
<i>KEK PS</i>	<i>1976</i>	<i>0.5Hz</i>	<i>trape.</i>	<i>SCR</i>
<i>SPring-8 syn.</i>	<i>1996</i>	<i>1Hz</i>	<i>trape.</i>	<i>SCR</i>
<i>JHF R&amp;D</i>	<i>1999</i>	<i>0.3Hz</i>	<i>trape.</i>	<i>IGBT</i>
<i>Tsukuba U.</i>	<i>2000</i>	<i>0.4Hz</i>	<i>trape.</i>	<i>IGBT</i>
<i>50GeV MR</i>	<i>2007</i>	<i>0.3Hz</i>	<i>trape.</i>	<i>IGBT/IEGT(120MVA)</i>


# Magnet Power Supply (R&D)

- \* *self-converter(PWM) type (high freq. switch. ~20kHz)*
- \* *no reactive power 100 % power factor*
- \* *ripple*  $\sim 10^{-6}$
- \* *tracking error*  $\sim 10^{-4}$



# RF Cavity with Magnetic Alloy

\* RF behaviour at high field       $E > 40 \text{ kV/m}$   
 $\propto Qf$  (shunt.imp.) vs.  $B_{rf}$




$B_{rf}$

# High Field Gradient RF Cavity with Magnetic Alloy


-MA Cavity-

*Field Gradient of RF Cavity*



## MA Cavity - Cut Core


\* Increase of Q-value with cut core  $\rightarrow$  curing beam loading



# High Gradient MA Cavity (R&D)

## \* Cooling (indirect)

- copper cooling plate
- keeping high shunt impedance




*core cutting with water-jet*

*MA Cavity*

## *Electro-static Septum (R&D)*

- \* *High Field* -> 237kV :achieved(1.4 x design voltage)
- \* *Need high quality ceramic feedthrough*



*ESS(R&D) assembly*

# *Summary* Linac Schedule Milestones



- **JFY01:** Most components for 200-MeV Linac and Bldg. to be ordered
- **Mid JFY02:** Most components for 400-MeV Linac to be ordered
- **Summer JFY04 :** Bldg. Completed, Installation to be started
- **March JFY05:** Commissioning to be started
- **Mid JFY 06:** Beam injection to RCS to be started

# *Summary* RCS Schedule Milestones




- JFY02: Half of components for and Bldg. to be ordered
- JFY03: Remaining half of components to be ordered
- March JFY04 : Bldg. Completed, Installation to be started
- Mid JFY06: Beam injection to RCS, that is, RCS commissionng to be started
- March JFY06: Beam extraction to the Neutron Source and to the 50-GeV Ring

# *Summary* 50-GeV Ring Schedule Milestones



- JFY01: Most of magnets and power supplies have been ordered.
- JFY02: Remaining components to be ordered
- Mid JFY05 : Bldg. Completed, Installation to be started
- March JFY06: Beam injection to the 50-GeV Ring and its commissioning to be started
- Mid JFY07: Beam extraction to the Nuclear and Particle Experimental area

# Summary schedule



*future upgrade*  
 $P_{beam} \sim 4\text{MW}$