

Status & plans of the SPL* study at CERN



1. Introduction
2. SPL principle and characteristics
3. On-going R&D
4. Staging
5. Summary and Conclusion

* SPL = Superconducting Proton Linac

*A concept for improving the performance of the protons beams at CERN,
ultimately based on a high-energy Superconducting Linear Accelerator*



The SPL Working Group



B. Autin, A. Blondel, **K. Bongardt**¹, O. Brunner, R. Cappi, **F. Caspers**, E. Cennini, **E. Chiaveri**, S. Claudet, **H. Frischholz**, R. Garoby, **F. Gerigk**⁴, K. Hanke, H. Haseroth, C. Hill, N. Hilleret, I. Hoffman², J. Inigo-Golfin, M. Jimenez, A. Krusche, D. Kuchler, M. Lindroos, **A. Lombardi**, R. Nunes, **R. Losito**, **M. Paoluzzi**, J. Pedersen, M. Poehler, H. Ravn, A. Rohlev³, R.D. Ryne³, M. Sanmarti, H. Schönauer, **M. Silari**, **J. Tuckmantel**, H. Vincke, A. Vital, C. Vollinger, **M. Vretenar**

¹ **KFZ Juelich, Germany**

² **GSI - Gesellschaft für Schwerionenforschung, Germany**

³ **LANL - Los Alamos National Laboratory, USA**

⁴ **RAL , Oxford, England**

others are from CERN, Switzerland

COLLABORATIONS


CEA (DSM/DAPNIA @ Saclay) + CNRS (IN2P3 @ Orsay & Grenoble): RFQ + DTL (IPHI)


INFN (Legnaro): RFQ

ITEP (Moscow): Room Temperature option between 120 – 240 MeV

REFERENCES

- Conceptual Design of the SPL, a High Power Superconducting Proton Linac at CERN Ed. M. Vretenar, CERN 2000-012
- SPL web site: http://cern.web.cern.ch/CERN/Divisions/PS/SPL_SG/





Applications and Benefits



◆ Approved physics experiments

- CERN Neutrinos to Gran Sasso (CNGS): increased flux ($\sim \times 2$)
- Anti-proton Decelerator: increased flux
- Neutrons Time Of Flight (TOF) experiments: increased flux
- ISOLDE: increased flux, higher duty factor, multiple energies
- LHC: faster filling time, increased operational margin

◆ Future potential users


- LHC performance upgrade beyond ultimate
- “Conventional” neutrino beam from the SPL “super-beam”
- Second generation ISOLDE facility (“EURISOL” -like)
- Neutrino source from “beta beams”
- Neutrino Factory



The Superconducting Proton Linac: Main Principles



- ◆ In line with modern High Power Proton Accelerator projects (SNS, JKJ,...)
- ◆ Re-use of the LEP RF equipment (SC cavities, cryostats, klystrons, waveguides, circulators, etc.)




The LEP klystron




Storage of the LEP cavities in the ISR tunnel



The Superconducting Proton Linac: Design (1)






The SPL: Design (2)



Section	Input energy (MeV)	Output energy (MeV)	No. of cavities	Peak RF power (MW)	No. of klystrons	No. of tetrodes	No. of Quads	Length (m)
Source, LEBT	-	0.045	-	-	-	-	-	2
RFQ	0.045	3	1	0.5	1	-	-	2.4
Chopper line	3	3	7	0.6	-	5	12	9.1
DTL	7	120	79	13.6	17	-	160	55
$\beta=0.52$	120	236	42	1.5	-	42	28	101
$\beta=0.7$	236	383	32	1.9	-	32	16	80
$\beta=0.8$ I	383	1111	52	9.5	13	-	26	166
$\beta=0.8$ II	1111	2235	76	14.6	19	-	19	237
Debunching	2235	2235	4	-	1	-	2	13
Total			293	42.2	51	79	263	665.5

54 cryostats,
32 directly from LEP,
the others reconstructed

51 LEP-type klystrons (44 used in LEP)



SPL Beam Specifications




	Parameter	Value	Unit
MEAN PARAMETERS	Ion species	H-	
	Kinetic energy	2.2	GeV
	Mean current during the pulse	13	mA
	Duty cycle [mean beam power]	14 [4]	% [MW]
	Pulse frequency	50	Hz
	Pulse duration [number of H- per pulse]	2.8 [2.27 E 14]	ms [H-/pulse]
FINE TIME STRUCTURE	Bunch frequency [minimum distance between bunches]	352.2 [2.84]	MHz [ns]
	Duty cycle during the beam pulse [number of successive bunches/number of buckets]	61.6 [5/8]	%
	Number of bunches in the accumulator [total number of buckets – empty buckets]	140 [146-6]	
	Maximum bunch current [maximum number of charges per bunch]	22 [3.85 E 8]	mA [H-/bunch]
BUNCH CHARACTERISTICS	Bunch length (total)	0.13	ns
	Energy spread (total) [relative momentum spread (total)]	1.2 [~ 0.42 E-3]	MeV
	Normalised horizontal emittance (1s)	0.6	mm
	Normalised vertical emittance (1s)	0.6	mm
	Energy jitter during the beam pulse	< +- 0.5	MeV
	Energy jitter between beam pulses	< +- 2	MeV

Revised parameters are in red




The Accumulator – Compressor Scheme



Two Rings in the ISR Tunnel

Accumulator:
 3.2 ms burst of 140 bunches at 44 MHz

Compressor:
 rms bunch length reduced to 1 ns




Characteristics of the beam sent to the target



Parameter	Value	Unit
Mean beam power	4	MW
Kinetic energy	2.2	GeV
Repetition rate	50	Hz
Pulse duration	3.3	μs
Number of bunches	140	
Pulse intensity	2.27×10^{14}	p/pulse
Bunch spacing (Bunch frequency)	22.7 (44)	ns (MHz)
Bunch length (σ)	1	ns
Relative momentum spread (σ)	5×10^{-3}	
Norm. horizontal emittance (σ)	50	$\mu\text{m}\cdot\text{rad}$





Layout on the CERN site





Cross section






SPL R&D Topics



- Minimise beam loss to avoid activation of the machine (loss < 1 W/m)
Beam Dynamics studies, optimise layout and beam optics
- Chopper structure to create a time distribution in the beam that minimises losses in the accumulator
Travelling wave deflector with rise time < 2 ns
- Efficient room-temperature section (W < 120 MeV)
CCDTL concept
- Development of SC cavities for $\beta < 1$
Sputtering techniques
- Pulsing of LEP klystrons
Built for CW, operated at 50 Hz, 14% duty
- Pulsing of SC cavities and effects of vibrations on beam quality
Low power (feedback), high power (phase and amplitude modulators) and active (piezos) compensation techniques




SPL R&D – Low Energy




Chopper structure

Full performance prototype tested
Driver amplifier in development



3 D view of a coupled cavity drift tube module (CCDTL)

Scaled model (1 GHz) in test



Source Low Energy section

DTL

Superconducting section

Debunching

Collaboration on RFQs with CEA-IN2P3 (IPHI) and INFN Legnaro

352 MHz test place prepared (planned tests of CEA-built DTL structures in 2002)




SPL R&D – CCDTL structures



CCDTL characteristics

Input Energy	40	MeV
Output Energy	120	MeV
Number of tanks	76	
Gradient	3	MV/m
Lattice	FD	
Max. surface field	1.3	Kilp.
Aperture radius	14	mm
Synchronous phase	-25	deg
Length	47	m
Real estate gradient	1.7	MeV/m
Number of quads	38	






SPL R&D – Low Beta SC Cavities



The $\beta=0.7$ 4-cell prototype

- ☆ CERN technique of Nb/Cu sputtering for $\beta=0.7$, $\beta=0.8$ cavities (352 MHz):
 - ⇒ excellent thermal and mechanical stability (very important for pulsed systems)
 - ⇒ lower material cost, large apertures, released tolerances, 4.5 °K operation with $Q = 10^9$




- ☆ Bulk Nb or mixed technique for $\beta=0.52$ (one 100 kW tetrode per cavity)




SPL R&D – Pulsing of LEP Klystrons




Mod anode driver



RF output power
(800 kW max.)



5 ns/div




1 µs/div



P LEP power supplies and klystrons are capable to operate in pulsed mode after minor modifications




SPL R&D – RF power distribution & field regulation in the SC cavities



Effect on field regulation



Effect on the beam



P unsolved problem ! Needs further investigation (high power phase & ampl. modulators, piezos,...)



SPL R&D – High power phase/amplitude modulator




Specifications:

Frequency: 352 MHz
Peak output power: 650 kW
Output power range: $\pm 10\%$
Output phase range: ± 22 deg.
Control speed: full range in 1 ms
Cost (series): < 20 kEuros



Can compensate for ± 20 Hz detuning of an SC cavity



High Power Phase & Amplitude Modulator



SPL R&D – Workplan in 2002



January	February	March	April	May	EPAC 2002	NuFact 2002	LINAC 2002	September	October	November	December
			Mini-workshop on 3 MeV test place (CEA, IN2P3,LNL)						SPL study review		
				Selection of RFQ output energy and chopper line design						Publication of the refined plans for the SPL study	
								Request for EURISOL support from E.U.			
Beam dynamics study and SPL design optimisation											
H- source development											
LLRF study and prototyping											
		Test prototype chopper driver									
		DTL tests with IPN (Grenoble) in PS South Hall									
							CCDTL tests in PS South Hall				
		Development of high power phase & amplitude modulator (AFT)									
Layout of the 120 MeV linac											
		Study of 120 MeV H- injection & accumulation in the PSB									
							Report on 120 MeV injector's proposal				




Staging



- ◆ **Test of a 3 (?) MeV H⁻ injector**
 - In collaboration with CEA-IN2P3 exploiting the IPHI set-up

- ◆ **120 MeV H⁻ linac in the PS South Hall [replacing LINAC 2 (50 MeV H⁺)]**
 - Goal: increase beam intensity for CNGS and improve characteristics of all proton beams (LHC, ISOLDE...)
 - Under study: detailed design report with cost estimate in 2003
 - Needs new resources (collaborations, manpower, money)

- ◆ **Full SPL**




120 MeV linac design



PARAMETERS	Phase 1 (PSB)	Phase 2 (SPL)						
Maximum repetition rate	2	50	Hz					
Source current *	50	30	mA					
RFQ current *	40	21	mA					
Chopper beam-on factor	75	62	%					
Current after chopper *	30	13	mA					
Pulse length (max.)	0.5	2.8	ms					
Average current	15	1820	μ A	at 1 Hz, resp. 50 Hz				
Max. beam duty cycle	0.1	14	%					
Max. number of particles per pulse	0.9	2.3	$\cdot 10^{14}$					
Transverse norm. emittance (rms)	0.25	0.25	π mm mrad					
Longitudinal emittance (rms)	0.3	0.3	π deg MeV					
Maximum design current	30		μ A	at 2 Hz				
Section	Input energy (MeV)	Output energy (MeV)	No. of cavities	Peak RF power (MW)	No. of klystrons	No. of tetrodes	No. of Quads	Length (m)
Source, LEBT	-	0.045	-	-	-	-	-	2
RFQ	0.045	3	1	0.5	1	-	-	3
Chopper line	3	3	5	0.5	-	5	12	6
DTL	3	120	13	11.9	15	-	149	64
TOTAL		120	19	12.9	16	5	161	75



The SPL Front-end (120 MeV) in the PS South Hall (intermediate proton intensity increase)




▮ Increased brightness for LHC, ~ 1.8 the flux to CNGS & ISOLDE, ... (with upgrades to the PSB, PS & SPS)

⇒ very **cost-effective** facility: hall and infrastructure are available in the PS
 all the RF is recuperated from LEP
 shielding is done with LEP dipoles!



The 120 MeV Linac



75 m

(100 m available in PS South Hall)



Summary and Conclusion



- ◆ **The SPL study is supported, although with limited resources, and progress is made:**
 - design is improving,
 - R&D is going on,
 - collaborations are active and more is encouraged !

- ◆ **A staged approach is proposed to:**
 - bring immediate benefits to the approved physics programme
 - help preserve and gradually strengthen a competent team
 - accelerate the realization of the complete SPL

- ◆ **Continuation after 2002 depends upon CERN management decisions to solve the LHC crisis...**